



PUBLIC WORKS DEPARTMENT

Airport General Maintenance Road Department Parks Transfer Stations

365 W. Highway 74
P.O. Box 428
Lexington, OR. 97839
Phone: (541) 989-9500
Fax: (541) 989-8352

Matt Scrivner
Public Works Director

Sandi Pointer
Management Asst.

Eric Imes
Asst. Road Master

Kirsti Cason
Administrative Asst.

Morrow County Public Works is requesting quotes for adding 1/8" steel panels to existing panels inside the Wilkinson Arena in Heppner, Oregon. The quote would be for the supply and installation of 1/8" steel on the below listed panels. The panel height would be 24" for all panels. 2"x2"x.125" square tubing will need to be installed on the bottom of each panel. MCPW would allow a 2" break in the metal instead of the square tubing as long as the vertical dimension of the panel is 24". Please note this option on your quote if chosen. All exterior edges must be welded with a 2 1/2" weld every 10 inches. Also the middle (Bottom rail on panels) must be welded to the same standard. Each exterior corner must be welded for 2 1/2" in each direction. All welds and panel edges must be wire brushed and ground smooth for safety reasons prior to painting. One coat of primer and One coat of Exterior grade paint to be installed after approval of installation of panels my Morrow County Public Works.

Panel sizes: 1-114"
1-78 1/4" gate
35-141 1/2" panels
2-48" gate
2-85 1/2" gate
1-102" gate
2-114" panel
2-60" gate
1-143 1/2" panel
1-126" gate

*Selected contractor shall field verify all dimensions onsite before construction.

Please submit quotes back to Morrow County Public Works by February 7th at 5:00pm. Contact for questions on this project will be Tony Clement 1-541-240-1791 aclement@co.morrow.or.us



EXIT

WARNING
BE CAREFUL WHEN
LEAVING LIVESTOCK

ANIMALS

Keep Gate
CLOSED

GLASS
LID
LID

